



## FT12HD

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

<b>Part Number</b>	FT12HD
<b>Safe Working Load (lbs)</b>	3,500
<b>Wall Size (in)</b>	12
<b>Filler Type</b>	Heavy Duty