



FT14HD

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

Part Number	FT14HD
Safe Working Load (lbs)	3,500
Wall Size (in)	14
Filler Type	Heavy Duty