



## FT11SP

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

<b>Part Number</b>	FT11SP
<b>Safe Working Load (lbs)</b>	3,000
<b>Wall Size (in)</b>	11
<b>Filler Type</b>	Standard