



## FT22SP

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

<b>Part Number</b>	FT22SP
<b>Safe Working Load (lbs)</b>	3,000
<b>Wall Size (in)</b>	22"
<b>Filler Type</b>	Standard