



FT30SP

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

| | |
|--------------------------------|----------|
| Part Number | FT30SP |
| Safe Working Load (lbs) | 3,000 |
| Wall Size (in) | 30 |
| Filler Type | Standard |