



FT84SP

OCM, Inc's X-Flat Ties are to be used in most steel ply modular forming systems utilizing wedge bolts to secure form work.

Part Number	FT84SP
Safe Working Load (lbs)	3,000
Wall Size (in)	84"
Filler Type	Standard